

PR SRT STD
U.S. Postage
PAID
Gemini Group
22901

City of Moberly
101 W Reed Street
Moberly, MO 65270

♻️ Recycled and Recyclable
Copyright ©2006 Gemini Group LLC
All rights reserved
MO1173

ANNUAL WATER QUALITY REPORT

Water testing performed in 2005

Proudly Presented By:



PWS ID#: MO2010533

How Is My Water Treated and Purified?

The treatment process consists of a series of steps. First, raw water is drawn from our water source and sent to an up-flow basin, where chemicals are added. The addition of these substances cause small particles to adhere to one another (called flocc), making them heavy enough to settle into a basin from which sediment is removed. Chlorine is then added for disinfection, and fluoride is added to prevent tooth decay. At this point, the water is filtered through layers of silica sand. As smaller, suspended particles are removed, turbidity disappears and clear water emerges. Chlorine is added again as a precaution against any bacteria that may still be present. (We carefully monitor the amount of chlorine, adding the lowest quantity necessary to protect the safety of your water without compromising taste.) Finally, the water is pumped to underground reservoirs, water towers and into your home or business.

Important Health Information

Some people may be more vulnerable to contaminants in drinking water than the general population. Immunocompromised persons such as persons with cancer undergoing chemotherapy, persons who have undergone organ transplants, people with HIV/AIDS or other immune system disorders, some elderly, and infants may be particularly at risk from infections. These people should seek advice about drinking water from their health care providers. The U.S. EPA/CDC (Centers for Disease Control and Prevention) guidelines on appropriate means to lessen the risk of infection by *Cryptosporidium* and other microbial contaminants are available from the Safe Drinking Water Hotline at (800) 426-4791.



Where Does My Water Come From?
The City of Moberly Water Treatment Plant draws water from Sugar Creek Reservoir, a lake covering approximately 365 acres. The Moberly Water Treatment Plant was constructed in 1972. Our treatment facility provides roughly 620 million gallons of clean drinking water every year.

Community Participation
You are invited to participate in our public forum and voice your concerns about your drinking water. We meet the first and third Monday of each month beginning at 7 p.m. at City Hall, 101 West Reed Street, Moberly, Missouri.

Substances That Might Be in Drinking Water

To ensure that tap water is safe to drink, the U.S. EPA prescribes regulations limiting the amount of certain contaminants in water provided by public water systems. U.S. Food and Drug Administration regulations establish limits for contaminants in bottled water, which must provide the same protection for public health. Drinking water, including bottled water, may reasonably be expected to contain at least small amounts of some contaminants. The presence of these contaminants does not necessarily indicate that the water poses a health risk. The sources of drinking water (both tap water and bottled water) include rivers, lakes, streams, ponds, reservoirs, springs, and wells. As water travels over the surface of land or through the ground, it can acquire naturally occurring minerals, in some cases, radioactive material, and substances resulting from the presence of animals or from human activity. Substances that may be present in source water include:

- Microbial Contaminants**, such as viruses and bacteria, which may come from sewage treatment plants, septic systems, agricultural livestock operations, or wildlife;
- Inorganic Contaminants**, such as salts and metals, industrial or domestic wastewater discharges, oil and gas production, mining, or farming;
- Pesticides and Herbicides**, which may come from a variety of sources such as agriculture, urban stormwater runoff, and residential uses;
- Organic Chemical Contaminants**, including synthetic and volatile organic chemicals, which are by-products of industrial processes and petroleum production, and which may also come from gas stations, urban stormwater runoff, and septic systems;
- Radioactive Contaminants**, which can be naturally occurring or may be the result of oil and gas production and mining activities.

For more information about contaminants and potential health effects, call the U.S. EPA's Safe Drinking Water Hotline at (800) 426-4791.

Continuing Our Commitment
Once again we proudly present our annual water quality report. This edition covers all testing completed from January through December 2005. We are pleased to tell you that our compliance with all state and federal drinking water laws remains exemplary. As in the past, we are committed to delivering the best quality drinking water. To that end, we remain vigilant in meeting the challenges of source water protection, water conservation, and community education while continuing to serve the needs of all of our water users. We have recently completed water filtration plant upgrades including raw water and high service pumps. Four new filters, including a carbon feed facility, now cover two sedimentation basins, and we have added a 16-inch high-service discharge line and approximately 17,000 feet of raw water supply piping. For more information about this report, or for any questions relating to your drinking water, please call Keith Phipps, Director of Public Utilities, at (660) 269-8705, ext. 2046.

Sampling Results

During the past year we have taken hundreds of water samples in order to determine the presence of any radioactive, biological, inorganic, volatile organic or synthetic organic contaminants. The table below shows only those contaminants that were detected in the water. Although all of the substances listed here are under the Maximum Contaminant Level (MCL), we feel it is important that you know exactly what was detected and how much of the substance was present in the water. The state requires us to monitor for certain substances less than once per year because the concentrations of these substances do not change frequently. In these cases, the most recent sample data are included, along with the year in which the sample was taken.

REGULATED SUBSTANCES

SUBSTANCE (UNITS)	YEAR SAMPLED	MCL	MCLG	AMOUNT DETECTED	RANGE LOW-HIGH	VIOLATION	TYPICAL SOURCE
Arsenic (ppb)	2005	10 ¹	0 ¹	1.04	1.04-1.04	No	Erosion of natural deposits; Runoff from orchards; Runoff from glass and electronics production wastes
Barium (ppm)	2005	2	2	0.103	0.103-0.103	No	Discharge of drilling wastes; Discharge from metal refineries; Erosion of natural deposits
Fluoride (ppm)	2005	4	4	1.0567	1.01-1.18	No	Erosion of natural deposits; Water additive which promotes strong teeth; Discharge from fertilizer and aluminum factories
HAA's [Haloacetic Acids] (ppb)	2005	60	NA	48.4125	26.8-77.9	No	By-product of drinking water disinfection
Nitrate (ppm)	2005	10	10	0.13	0.13-0.13	No	Runoff from fertilizer use; Leaching from septic tanks, sewage; Erosion of natural deposits
Total Organic Carbon (ppm)	2005	TT	NA	4.4846	2.33-7.03	No	Naturally present in the environment
TTHMs [Total Trihalomethanes] (ppb)	2005	80	NA	51.9250	17.5-96	No	By-product of drinking water disinfection
Turbidity (NTU) ²	2005	TT	NA	0.44	ND-0.44	No	Soil runoff

Tap water samples were collected for lead and copper analyses from 30 homes throughout the service area

SUBSTANCE (UNITS)	YEAR SAMPLED	ACTION LEVEL	MCLG	AMOUNT DETECTED (90TH% TILE)	HOMES ABOVE ACTION LEVEL	VIOLATION	TYPICAL SOURCE
Copper (ppm)	2004	1.3	1.3	0.264	0	No	Corrosion of household plumbing systems; Erosion of natural deposits; Leaching from wood preservatives
Lead (ppb)	2004	15	0	9.20	1	No	Corrosion of household plumbing systems; Erosion of natural deposits

UNREGULATED SUBSTANCES

SUBSTANCE (UNITS)	YEAR SAMPLED	AMOUNT DETECTED	RANGE LOW-HIGH	TYPICAL SOURCE
Chloroform (ppb)	2005	44.2716	12.1-88.1	By-product of drinking water disinfection
Bromochloroacetic Acid (ppb)	2005	0.6038	ND-3.81	By-product of drinking water disinfection
Bromodichloroacetic Acid (ppb)	2005	3.4162	ND-5.44	By-product of drinking water disinfection
Bromodichloromethane (ppb)	2005	6.3647	4.01-9.85	By-product of drinking water disinfection
Chlorodibromomethane (ppb)	2005	0.4259	ND-1.22	By-product of drinking water disinfection
Nickel (ppm)	2005	2.390	2.39-2.39	Naturally present in the environment
Trichloroacetic Acid (ppb)	2005	25.1875	13.5-37.3	By-product of drinking water disinfection

About Our Violation

During the period of June 1 to June 30, 2005, we had a minor monitoring violation for the interim enhanced surface water treatment rule. We are required to monitor and record turbidity from each filter every 15 minutes when the filter is operating. A failure in the monitoring equipment kept data from being recorded during a period of the day. Within eight days, this problem was corrected and the system was functioning properly again. While the equipment was down, turbidity levels were visually monitored and all water was safe for consumption.

Contamination from Cross-Connections

Cross-connections that could contaminate drinking water distribution lines are a major concern. A cross-connection is formed at any point where a drinking water line connects to equipment (boilers), systems containing chemicals (air conditioning systems, fire sprinkler systems, irrigation systems) or water sources of questionable quality. Cross-connection contamination can occur when the pressure in the equipment or system is greater than the pressure inside the drinking water line (backpressure). Contamination can also occur when the pressure in the drinking water line drops due to fairly routine occurrences (main breaks, heavy water demand), causing contaminants to be sucked out from the equipment and into the drinking water line (backsiphonage).

Outside water taps and garden hoses tend to be the most common sources of cross-connection contamination at home. The garden hose creates a hazard when submerged in a swimming pool or when attached to a chemical sprayer for weed killing. Garden hoses that are left lying on the ground may be contaminated by fertilizers, cesspools or garden chemicals. Improperly installed valves in your toilet could also be a source of cross-connection contamination.

Community water supplies are continually jeopardized by cross-connections unless appropriate valves, known as backflow prevention devices, are installed and maintained. We have surveyed all industrial, commercial, and institutional facilities in the service area to make sure that all potential cross-connections are identified and eliminated or protected by a backflow preventer. We also inspect and test each backflow preventer to make sure that it is providing maximum protection.

For more information, visit the Web site of the American Backflow Prevention Association (www.abpa.org) for a discussion on current issues.



Table Definitions

AL (Action Level): The concentration of a contaminant which, if exceeded, triggers treatment or other requirements which a water system must follow.

MCL (Maximum Contaminant Level): The highest level of a contaminant that is allowed in drinking water. MCLs are set as close to the MCLGs as feasible using the best available treatment technology.

MCLG (Maximum Contaminant Level Goal): The level of a contaminant in drinking water below which there is no known or expected risk to health. MCLGs allow for a margin of safety.

NA: Not applicable

ND: Not detected

NTU (Nephelometric Turbidity Units): Measurement of the clarity, or turbidity, of water.

ppb (parts per billion): One part substance per billion parts water (or micrograms per liter).

ppm (parts per million): One part substance per million parts water (or milligrams per liter).

TT (Treatment Technique): A required process intended to reduce the level of a contaminant in drinking water.

Footnotes:

¹ These arsenic values were effective January 23, 2006; however, during 2005 the MCL was 50 ppb and there was no MCLG.

² Turbidity is a measure of the cloudiness of the water. We monitor it because it is a good indicator of the effectiveness of our filtration system. During the reporting year, a minimum of 99% of all samples taken to measure turbidity met water quality standards.




Lead in Drinking Water

Lead is a naturally occurring element in our environment. Consequently, our water supply is expected to contain small, undetectable amounts of lead. However, most of the lead in household water usually comes from the plumbing in your own home, not from the local water supply. The U.S. EPA estimates that more than 40 million U.S. residents use water that can contain lead in excess of EPA's Action Level of 15 ppb.

Lead in drinking water is a concern because young children, infants and fetuses appear to be particularly vulnerable to lead poisoning. A dose that would have little effect on an adult can have a big effect on a small body. On average, it is estimated that lead in drinking water contributes between 10% and 20% of the total lead exposure in young children.

All kinds of water, however, may have high levels of lead. We maintain our drinking water supply at an optimum pH and mineral content level to help prevent corrosion in your home's pipes. To reduce lead levels in your drinking water you should flush your cold-water pipes by running the water until it becomes as cold as it will get (anywhere from five seconds to two minutes or longer) and use only water from the cold-water tap for drinking, cooking, and especially for making baby formula. Hot water is likely to contain higher levels of lead.

For more information, please call the Safe Drinking Water Hotline at (800) 426-4791.



Water Conservation Tips

Water conservation measures are an important first step in protecting our water supply. Such measures not only save the supply of our source water but can also save you money by reducing your water bill. Here are a few suggestions:

Inside your home:

- Fix leaking faucets, pipes, toilets, etc.
- Replace old fixtures; install water-saving devices in faucets, toilets, and appliances.
- Wash only full loads of laundry.
- Do not use the toilet for trash disposal.
- Take shorter showers.
- Do not let the water run while shaving or brushing teeth.
- Soak dishes before washing.
- Run the dishwasher only when full.

Outdoors:

- Water the lawn and garden in the early morning or evening.
- Use mulch around plants and shrubs.
- Repair leaks in faucets and hoses.
- Use water-saving nozzles.
- Use water from a bucket to wash your car, and save the hose for rinsing.

Information on other ways that you can help conserve water can be found at www.epa.gov/safewater/publicoutreach/index.html.